



TYPICAL CROSS SECTION (SCHEMATIC)




Layer thicknesses not to scale (vertical exaggeration). Longitudinal joints with tie bars shown dashed.



SLAB LAYOUT - JOINTS, DOWEL AND TIE BARS (PLAN)


SCALE 1:125



CONTRACTION JOINT WITH DOWEL BAR

SCALE 1:10

Dowel 38 dia x 500 mm, half length de-bonded




LONGITUDINAL JOINT WITH TIE BAR

SCALE 1:10

Tie bar 12 dia deformed x 640 mm

CFD vs SLAB THICKNESS



DESIGN SUMMARY (IRC:58-2015)

Design thickness (CFD <= 1)	290 mm
Adopted PQC thickness	300 mm (incl. 10 mm for retexturing)
CFD bottom-up / top-down	0.282 / 0.253
Total CFD	0.535 <= 1.0
Effective k of foundation	283.6 MPa/m
Design flexural strength	4.95 MPa (90-day)
Temperature differential day / night	16.8 / 13.4 deg C
Radius of relative stiffness l	685 mm
Design traffic (CVs, design period)	226.44 million
Axle repetitions BUC / TDC (6 h)	13.30 / 10.98 million
Dowel bars	38 mm dia x 500 mm @ 300 mm c/c
Tie bars	12 mm deformed x 640 mm @ 590 mm c/c
Contraction joint spacing	4.5 m

Result: **SAFE - CFD <= 1**

NOTES

- All dimensions in mm unless noted otherwise.
- PQC to MORTH Section 600; DLC 7 MPa at 7 days (IRC:SP:49).
- Polythene 125 micron de-bonding layer between DLC and PQC.
- Dowels plain MS, half length de-bonded; tie bars to IS 1786.
- Joints sawn and sealed as per IRC:57; spacing <= 4.5 m.

IRC 58 example check

Rigid pavement 300 mm PQC

Designed: - Checked: -

Date: 31 Oct 2026 Scale: as shown Sheet 1 of 1