

ESTIMATE AND BILL OF QUANTITIES

SOUTH UDA UDAIPUR

Name of work	SOUTH UDA UDAIPUR
Client	-
Location	-
Prepared by	-
Features measured	2
Total estimated cost	■ 2,27,44,991
Date	31 Oct 2026

Lengths measured on the map

Feature type	Length (m)
Side drain	292.3
Road / carriageway	658.5

Abstract of cost

S. no.	Description	Amount (■)
1	Earthwork	53,76,592
2	Pavement	1,18,91,388
3	Structures	12,53,407
4	Road furniture	1,92,609
	Sub-total	1,87,13,996
6	Contingencies @ 3 %	5,61,420
7	GST @ 18 %	34,69,575
	Total estimated cost	2,27,44,991

Bill of quantities

No.	Description of item	Unit	Quantity	Rate (₹)	Amount (₹)
	EARTHWORK				
1	Clearing and grubbing of road land	m ²	19,754.78	25	4,93,869
2	Construction of embankment with approved material, compacted	m ³	8,560.40	380	32,52,953
3	Construction of subgrade, compacted, CBR ≥ 8 %	m ³	3,621.71	450	16,29,769
	Total - Earthwork				53,76,592
	PAVEMENT				
4	Bituminous concrete (BC) Grading II	m ³	184.38	11,500	21,20,346
5	Dense bituminous macadam (DBM) Grading II	m ³	276.57	9,800	27,10,355
6	Granular sub-base (GSB) Grading I	m ³	1,396.00	2,100	29,31,609
7	Prime coat over granular base	m ²	4,807.00	45	2,16,315
8	Granular / earthen shoulder, compacted	m ³	691.42	900	6,22,275
9	Tack coat	m ²	9,218.90	18	1,65,940
10	Wet mix macadam (WMM)	m ³	1,201.75	2,600	31,24,547
	Total - Pavement				1,18,91,388
	STRUCTURES				
11	PCC M15 levelling course / bedding	m ³	35.08	5,600	1,96,454
12	RCC M25 in structures (excluding steel)	m ³	92.09	8,200	7,55,118
13	Reinforcement Fe 500D - supply, cut, bend and place	t	2.72	78,000	2,12,378
14	Excavation for structures, incl. backfilling	m ³	298.19	300	89,457
	Total - Structures				12,53,407
	ROAD FURNITURE				
15	Thermoplastic road marking 2.5 mm	m ²	296.32	650	1,92,609
	Total - Road furniture				1,92,609
	Sub-total (carried to abstract)				1,87,13,996

Detailed estimate - item-wise measurements

Each quantity = Nos × L × B × D (metres). Locations are chainages along the drawn features; numbers in brackets refer to the feature list and layout plan.

No.	Description / location	Nos	L	B	D / H	Quantity	Unit
1	Clearing and grubbing of road land						
	(2) Road / carriageway 2, Ch. 0+000.00 to 0+658.49: Clearing and grubbing of road land	1	658.493	30.000		19,754.777	m ²
	Total item 1					19,754.777	m ²
2	Construction of embankment with approved material, compacted						
	(2) Road / carriageway 2, Ch. 0+000.00 to 0+658.49: Embankment: mean width = top 11 + 2 × 1 (side slopes 2H:1V)	1	658.493	13.000	1.000	8,560.403	m ³
	Total item 2					8,560.403	m ³
3	Construction of subgrade, compacted, CBR ≥ 8 %						
	(2) Road / carriageway 2, Ch. 0+000.00 to 0+658.49: Subgrade 500 mm (0.5 m extra each side)	1	658.493	11.000	0.500	3,621.709	m ³
	Total item 3					3,621.709	m ³
4	Bituminous concrete (BC) Grading II						
	(2) Road / carriageway 2, Ch. 0+000.00 to 0+658.49: BC 40 mm over carriageway	1	658.493	7.000	0.040	184.378	m ³
	Total item 4					184.378	m ³
5	Dense bituminous macadam (DBM) Grading II						
	(2) Road / carriageway 2, Ch. 0+000.00 to 0+658.49: DBM 60 mm over carriageway	1	658.493	7.000	0.060	276.567	m ³
	Total item 5					276.567	m ³
6	Granular sub-base (GSB) Grading I						
	(2) Road / carriageway 2, Ch. 0+000.00 to 0+658.49: GSB 200 mm (0.3 m extra each side)	1	658.493	10.600	0.200	1,396.004	m ³
	Total item 6					1,396.004	m ³
7	Prime coat over granular base						
	(2) Road / carriageway 2, Ch. 0+000.00 to 0+658.49: Prime coat on WMM (0.15 m extra each side)	1	658.493	7.300		4,806.996	m ²
	Total item 7					4,806.996	m ²
8	Granular / earthen shoulder, compacted						
	(2) Road / carriageway 2, Ch. 0+000.00 to 0+658.49: Granular / earthen shoulders, depth = pavement thickness	2	658.493	1.500	0.350	691.417	m ³
	Total item 8					691.417	m ³
9	Tack coat						
	(2) Road / carriageway 2, Ch. 0+000.00 to 0+658.49: Tack coat on DBM (below BC)	1	658.493	7.000		4,609.448	m ²
	Tack coat on primed WMM (below DBM)	1	658.493	7.000		4,609.448	m ²
	Total item 9					9,218.896	m ²
10	Wet mix macadam (WMM)						
	(2) Road / carriageway 2, Ch. 0+000.00 to 0+658.49: WMM 250 mm (0.15 m extra each side)	1	658.493	7.300	0.250	1,201.749	m ³
	Total item 10					1,201.749	m ³
11	PCC M15 levelling course / bedding						
	(1) Side drain 1, Ch. 0+000.00 to 0+292.34: PCC M15 levelling course 100 mm	1	292.342	1.200	0.100	35.081	m ³
	Total item 11					35.081	m ³
12	RCC M25 in structures (excluding steel)						
	(1) Side drain 1, Ch. 0+000.00 to 0+292.34: RCC M25 side walls 0.15 m thick	2	292.342	0.150	0.600	52.621	m ³
	RCC M25 base slab, outer width 0.9 m	1	292.342	0.900	0.150	39.466	m ³
	Total item 12					92.088	m ³
13	Reinforcement Fe 500D - supply, cut, bend and place						
	(1) Side drain 1, Ch. 0+000.00 to 0+292.34: Reinforcement Fe500D as designed (IS 456): 9.31 kg per m of drain incl. 5 % laps - t per m	1	292.342	0.009		2.723	t
	Total item 13					2.723	t

No.	Description / location	Nos	L	B	D / H	Quantity	Unit
14	Excavation for structures, incl. backfilling						
	(1) Side drain 1, Ch. 0+000.00 to 0+292.34: Excavation (one side): outer width 0.9 + 0.3 working space	1	292.342	1.200	0.850	298.188	m ³
	Total item 14					298.188	m ³
15	Thermoplastic road marking 2.5 mm						
	(2) Road / carriageway 2, Ch. 0+000.00 to 0+658.49: Road marking - centre and edge lines, 150 mm wide	3	658.493	0.150		296.322	m ²
	Total item 15					296.322	m ²

Feature-wise cost

No.	Feature	Type	Location	Length (m)	Drawing	Amount (■)
1	Side drain 1	Side drain	Ch. 0+000.00 to 0+292.34	292.3	D-1	12,53,407
2	Road / carriageway 2	Road / carriageway	Ch. 0+000.00 to 0+658.49	658.5	D-2	1,74,60,589
	Total (before contingencies and taxes)					1,87,13,996

Layout plan



Numbers refer to the feature list, the detailed estimate and the drawings: feature (n) is shown on drawing D-n. Geometry as drawn on the map (WGS 84); lengths are geodesic.

Drawings - typical sections and details

Drawing D-n shows feature (n) of the layout plan, drawn from the inputs used for its quantities. Dimensions in mm unless noted; sections are typical along the whole length of the feature.


D-1

(1) Side drain 1 - Side drain

Ch. 0+000.00 to 0+292.34, 292.3 m

RCC OPEN DRAIN

one side of the road



dimensions in mm

Drain type	RCC open U-drain	Drain on	One side
Clear width (m)	0.6	Clear depth (m)	0.6
Wall thickness (m)	0.15	Base slab thickness (m)	0.15
Concrete grade (walls, base, cover)	M25	PCC levelling course (mm)	100
PCC levelling grade	M15	Steel grade	Fe500D
Reinforcement	Design to IS 456 (walls, base, cover slab)	Clear cover to bars (mm)	40
Soil unit weight (kN/m³)	18	Angle of internal friction φ (deg)	30
Surcharge next to the drain (kN/m²)	10	Side wall (each) - main / distribution	8φ @ 250 c/c / 8φ @ 250 c/c
Base slab - main / distribution	8φ @ 250 c/c / 8φ @ 250 c/c	Reinforcement per m of drain	9.31 kg (incl. 5 % laps)


D-2

(2) Road / carriageway 2 - Road / carriageway

Ch. 0+000.00 to 0+658.49, 658.5 m

ROAD - TYPICAL CROSS SECTION

1 × 7 m carriageway, earthen shoulders 1.5 m



Pavement data	Simple: carriageway + shoulders	Pavement type	Flexible (bituminous)
Carriageway width (m)	7	Number of carriageways	1
Shoulder width each side (m)	1.5	Shoulder	Granular / earthen
BC thickness (mm)	40	DBM thickness (mm)	60
WMM thickness (mm)	250	GSB thickness (mm)	200
Subgrade thickness (mm)	500	Average embankment height (m)	1
Average cutting depth (m)	0	Side slope (H : 1V)	2
Width of land to clear (m)	30	Road marking (centre + edge lines)	Yes